

Team 7: Microalgae Photobioreactor Midterm I (Spring Presentation)



Stephen Kassing, Markus Dillman, Matthew Vedrin

Project Advisors:

Dr. Juan Ordonez (Department of Mechanical Engineering, FSU)

Dr. José Vargas (Department of Mechanical Engineering, UFPR)

Presentation Outline

- Background and Project Scope
- Microalgae Growth
- Airlift Photobioreactor Design
- Control Design
- Addition/Extraction Unit Design
- Budget and Flow Chart Schedule
- Conclusion and Questions



Background and Project Scope

Goal: Microalgae  Biofuel

The customer needs a way to transform an airlift photobioreactors' current "batch" growth systems into a "semi-continuous growth systems."

To accomplish this team 7 must:


- ✓ Find an affective and efficient way to grow microalgae
- ✓ Improve last semesters concentration and mass flow sensor
 - ✓ Design an build a 35L Airlift Photobioreactor
- ✓ Design and develop fully automated addition/extraction units

Algae Growth


- Currently have about 20 Liters of microalgae
- In the next couple of weeks we will subculture the algae to 50L
- Algae growth curves have been produced this semester to log the cell concentration



Cell Counting




Current batches of microalgae being grown this semester.



Batch 4 cell growth chart.

Airlift Photobioreactor

- What is a photobioreactor?
 - A container that grows living organisms using light.
- Why are we building a new unit?
 - Successful design from Brazil.
 - Less water hammering.
 - Allows us to perform testing on a smaller scale.



Controls – Overview

Batch operation: manual labor is reasonable

Semi-continuous operation: manual labor is not viable


Conclusion: Automated control systems needed



Concentration



Mass Flow



Addition/Extraction

Controls – Concentration Sensor


Current Design

Electrical Components:

- Light Emitting Diode (LED)
- Light Dependent Resistor (LDR)



Main Sections:

- **Control**
 - Full Light
- **Test**
 - Variable Light
- **Wheatstone Bridge**
 - Control & Test LDR's
 - Noise & Sensitivity




Controls – Concentration Sensor

Preliminary Tests – Food Dye





Controls – Final Goal

Control Flow




Addition and Extraction Design

- 1- Extraction Cycle
- 2- Addition Cycle



Current Expenditures for Spring Semester



Flow Chart Schedule

WEEK 2 (Jan. 13-19)

- ✓ Create Pro-E CAD of new airlift photobioreactor
- ✓ Start counting cells to establish microalgae growth curve



WEEK 3 (Jan. 20-26)

- ✓ Complete bill of materials and procurement for airlift photobioreactor (not new units)
- ✓ Finalize CAD and order pipes and fittings for Airlift (not the new units)



WEEK 5 (Feb. 3-9)

- ✓ All Parts for airlift photobioreactor arrive at College of Engineering
- ✓ Perform Tests on Concentration Sensor
- ✓ Set up first meeting with chemical engineering students about counting algae



WEEK 6 (Feb. 10-16)

- ✓ Design I Presentation
- ✓ Assemble all parts and check water integrity of airlift (not including new sensors)
- ✓ Perform airlift flow test (not including new sensors)
- ✓ Create CAD with airlift and new addition/extraction units
- ✓ Order parts for addition and extraction units



WEEK 7 (Feb. 17-23)

- ✓ Start to assemble new addition and extraction units
- ✓ Perform water integrity tests with new units attached to photobioreactor



Thank You


Any Questions?

Control Sensors – Concentration Sensor

2012-2013

Wheatstone Bridge:

- Range of LDR Resistance Values
 - Full Light = $1\text{k}\Omega$
 - No Light = $100\text{k}\Omega$
- Working LDR (varies) $\rightarrow 1\text{-}100\text{k}\Omega$
- Control LDR (full light) $\rightarrow 1\text{k}\Omega$
- Arduino Reading = $V_{\text{aref}} - V_{\text{input}}$



Source: 2012-2013 Microalgae Senior Design Team